



K.S. GROUP OF INSTITUTIONS
K.S. SCHOOL OF ENGINEERING & MANAGEMENT

#15/1, Mallasandra, Off. Kanakapura Main Road, Bengaluru - 560 109
Phone : 080 2842 5012, 2842 5013, 2842 5163 | Fax : 080 -2842 5164

RECEIPT

No. **9947**

Date : 22/12/2020

Received From Mr. / Miss Sri Vatsa - ev Dept

..... studying in B.E / MBA / M.Tech

a sum of Rupees four hundred rupees only

towards the Library fine / Xerox / Shortage of attendance / lab. Breakage / Miscellaneous

Towards cube Testing

Rs. 400/-


Accountant



KAMMAVARI SANGHAM (R), 1952

K. S. School of Engineering and Management

Approved by AICTE-1-5279601, Affiliated to VTU, Belagavi
#15, Near Vajarahalli, Mallasandra, off Kanakapura Road,
Bengaluru - 560 109, www.kssem.edu.in

Tel: +91 80 28425012/013/163, Fax: +91 80 28425164, Mob: 8884444408

Department of Civil Engineering

Test report


Date: 22nd Dec 2020

To
V Consultancy

1 set of 3 concrete cubes were sent for compressive strength test. The test was conducted and results are described as below.

Date of testing: 22nd Dec 2020

Sl. No.	Cube No.	Date of Cast	Weight (kg)	Compressive strength (N/mm ²)	Avg. Strength (N/mm ²)	Remarks
1	C1	15/12/2020	8.40	25.84	25.54	7 days Strength
2	C2	15/12/2020	8.52	25.23		
3	C3	29/11/2020	8.50	24.14	24.14	21 days Strength


Signature of staff


Head of Department

Department of Civil Engineering

Professor & Head
Dept. of Civil Engineering
K.S. Group of Institutions
K.S. School of Engineering & Management
Bangalore-560 062.



K.S. GROUP OF INSTITUTIONS
K.S. SCHOOL OF ENGINEERING & MANAGEMENT

#15/1, Mallasandra, Off. Kanakapura Main Road, Bengaluru - 560 109
Phone : 080 2842 5012, 2842 5013, 2842 5163 | Fax : 080 -2842 5164

RECEIPT

No. **9977**

Date : **15/1/2021**

Received From Mr. / Miss **Civil Dept (Concrete Lab)**
..... studying in **B.E / MBA / M.Tech**
a sum of Rupees **Two Hundred Rupees only**
towards the Library fine / Xerox / Shortage of attendance / lab. Breakage / Miscellaneous

Tube test

Rs. **200/-**

Accountant



KAMMAVARI SANGHAM (R), 1952

K. S. School of Engineering and Management

Approved by AICTE-1-5279601, Affiliated to VTU, Belagavi
#15, Near Vajarahalli, Mallasandra, off Kanakapura Road,
Bengaluru – 560 109, www.kssem.edu.in

Tel: +91 80 28425012/013/163, Fax: +91 80 28425164, Mob: 8884444408

Department of Civil Engineering

Test report

Date: 15th Sep 2020

To
V Consultancy

1 set of 2 concrete cubes were sent for compressive strength test. The test was conducted and results are described as below.

Date of testing: 15th Sep 2020

Sl. No.	Cube No.	Date of Cast	Weight (kg)	Compressive strength (N/mm ²)	Avg. Strength (N/mm ²)	Remarks
1	C1	06/09/2020	8.22	11.00	12.60	7 days Strength
2	C2	06/09/2020	8.45	14.20		

B.M
Signature of staff

V. K. Kelle
Head of Department

Department of Civil Engineering

Professor & Head
Dept. of Civil Engineering
K.S. Group of Institutions
K.S. School of Engineering & Management
Bangalore-560 062.



K.S. GROUP OF INSTITUTIONS
K.S. SCHOOL OF ENGINEERING & MANAGEMENT

#15/1, Mallasandra, Off. Kanakapura Main Road, Bengaluru - 560 109
Phone : 080 2842 5012, 2842 5013, 2842 5163 | Fax : 080 -2842 5164

RECEIPT

No. **9905**

Date : 18/11/2020

Received From Mr. / Miss Srivatsa (CV-consultancy)

CV-Dept studying in B.E / MBA / M.Tech

a sum of Rupees five hundred only.

towards the Library fine / Xerox / Shortage of attendance / lab. Breakage / Miscellaneous

cube Testing

Rs. 500/-

[Signature]
Accountant



KAMMAVARI SANGHAM (R), 1952
K. S. School of Engineering and Management

Approved by AICTE-1-5279601, Affiliated to VTU, Belagavi
#15, Near Vajarahalli, Mallasandra, off Kanakapura Road,
Bengaluru – 560 109, www.kssem.edu.in

Tel: +91 80 28425012/013/163, Fax: +91 80 28425164, Mob: 8884444408

Department of Civil Engineering

Test report

Date: 9th Nov 2020

To
V Consultancy

1 set of 3 concrete cubes were sent for compressive strength test. The test was conducted and results are described as below.

Date of testing: 09th Nov 2020

Sl. No.	Cube No.	Date of Cast	Weight (kg)	Compressive strength (N/mm ²)	Avg. Strength (N/mm ²)	Remarks
1	C1	19/09/2020	8.48	20.8	18.73	21 days Strength
2	C2	19/09/2020	8.50	16.66		
3	C3	12/09/2020	8.45	28.31	28.31	28 days Strength

Signature of staff

Head of Department

Department of Civil Engineering

Professor & Head

Dept. of Civil Engineering

K.S. Group of Institutions

K.S. School of Engineering & Management

Bangalore-560 062.



KSSEM
K.S. SCHOOL OF ENGINEERING & MANAGEMENT

KAMMAVARI SANGHAM (R), 1952

K. S. School of Engineering and Management

Approved by AICTE-1-5279601, Affiliated to VTU, Belagavi
#15, Near Vajarahalli, Mallasandra, off Kanakapura Road,
Bengaluru – 560 109, www.kssem.edu.in

Tel: +91 80 28425012/013/163, Fax: +91 80 28425164, Mob: 8884444408

Department of Civil Engineering

Test report

Date: 22nd Dec 2020

To
V Consultancy

1 200x200x200mm size Clay block and 1 concrete cubes were sent for compressive strength test.
The test was conducted and results are described as below.

Date of testing: 22nd Dec 2020

Sl. No.	Cube No. / Block No.	Date of Cast	Weight (kg)	Compressive strength (N/mm ²)	Avg. Strength (N/mm ²)	Remarks
1	B1	-	-	1.58	1.58	-
2	C1	15/11/2020	8.32	16.8	16.8	7 days Strength

By
Signature of staff

W. Kelle
Head of Department
Department of Civil Engineering

Professor & Head
Dept. of Civil Engineering
K.S. Group of Institutions
K.S. School of Engineering & Management
Bangalore-560 102.



KAMMAVARI SANGHAM (R), 1952

K. S. School of Engineering and Management

Approved by AICTE-1-5279601, Affiliated to VTU, Belagavi
#15, Near Vajarahalli, Mallasandra, off Kanakapura Road,
Bengaluru – 560 109, www.kssem.edu.in

Tel: +91 80 28425012/013/163, Fax: +91 80 28425164, Mob: 8884444408

Department of Civil Engineering

Test report


Date: 26th June 2020


To
V Consultancy

1 set of 2 concrete cubes were sent for compressive strength test. The test was conducted and results are described as below.

Date of testing: 26th June 2020

Sl. No.	Cube No.	Date of Cast	Weight (kg)	Compressive strength (N/mm ²)	Avg. Strength (N/mm ²)	Remarks
1	C1	19/06/2020	8.50	12.78	12.74	7 days Strength
2	C2	19/06/2020	8.45	12.70		


Signature of staff


Head of Department

Department of Civil Engineering

Professor & Head
Dept. of Civil Engineering
K.S. Group of Institutions
K.S. School of Engineering & Management
Bangalore-560 062.



KSSEM

**K.S. GROUP OF INSTITUTIONS
K.S. SCHOOL OF ENGINEERING & MANAGEMENT**

#15/1, Mallasandra, Off. Kanakapura Main Road, Bengaluru - 560 109
Phone : 080 2842 5012, 2842 5013, 2842 5163 | Fax : 080 -2842 5164

RECEIPT

No. **9632**

Date : **13/07/2020**

Received From Mr. / Miss **Bhaskar** - **CV Dept**

..... studying in **B.E / MBA / M.Tech**

a sum of Rupees **Three hundred rupees only**

towards the Library fine / Xerox / Shortage of attendance / lab. Breakage / Miscellaneous

solid Blocks testing

Rs. **300/-**


Accountant



KAMMAVARI SANGHAM (R), 1952
K. S. School of Engineering and Management

Approved by AICTE-1-5279601, Affiliated to VTU, Belagavi
#15, Near Vajarahalli, Mallasandra, off Kanakapura Road,
Bengaluru – 560 109, www.kssem.edu.in


Tel : +91 80 28425012/013/163, Fax : +91 80 28425164, Mob : 8884444408

Test Report

Date: 13-07-2020

Details of test report of cement Solid blocks submitted by Mr. Bhaskara J.

Sl. No.	Block Trade Name	Block Name	Block dimensions (mm)	Crushing Load (kN)	Block Weight (kg)	Block Strength (N/mm ²)
1	8" Solid	APCO	402X199X200	892.2	34.85	11.19
2	Concrete Blocks	Normal	406X200X198	771.6	34.52	9.50


Signature of staff tested


HOD
Department of Civil Engineering
Professor & Head
Dept. of Civil Engineering
K.S. Group of Institutions
K.S. School of Engineering & Management
Bangalore-560 062.



KSSEM

**K.S. GROUP OF INSTITUTIONS
K.S. SCHOOL OF ENGINEERING & MANAGEMENT**

#15/1, Mallasandra, Off. Kanakapura Main Road, Bengaluru - 560 109
Phone : 080 2842 5012, 2842 5013, 2842 5163 | Fax : 080 -2842 5164

RECEIPT

No. **9616**

Date : 1/6/2020

Received From Mr. / Miss Manjunath. B. - CIVIL Dept.

..... studying in B.E / MBA / M.Tech

a sum of Rupees seven hundred and fifty rupees only.

towards the Library fine / Xerox / Shortage of attendance / lab. Breakage / Miscellaneous

Towards NDT Testing

Rs. 750/-


Accountant



K.S. SCHOOL OF ENGINEERING AND MANAGEMENT
BENGALURU – 560109
DEPARTMENT OF CIVIL ENGINEERING

TEST REPORT

Date: 31/05/2020

Client: VAGDEVI Group of schools
Verthur, Bengaluru

Mail id: -

Type: Footing in the site

Grade of Concrete: M30*

Test: Rebound hammer test

Visited the site and tested the compressive strength of footings by using NDT (Rebound hammer test). The test was conducted and results are described as below.

Sl. No.	FOOTING NUMBER	DATE OF CASTING	DATE OF TESTING	COMPRESSIVE STRENGTH (N/mm ²)
1	F1	23/05/2020	30/05/2020	26.50
2	F2	23/05/2020	30/05/2020	21.21
3	F3	23/05/2020	30/05/2020	23.90
4	F4	23/05/2020	30/05/2020	18.75
5	F5	23/05/2020	30/05/2020	19.08
6	F6	23/05/2020	30/05/2020	23.92
7	F7	23/05/2020	30/05/2020	24.14
8	F8	23/05/2020	30/05/2020	25.00
9	F9	23/05/2020	30/05/2020	28.50
10	F10	23/05/2020	30/05/2020	27.75
11	F11	23/05/2020	30/05/2020	18.16
12	F12	23/05/2020	30/05/2020	23.70
13	F13	23/05/2020	30/05/2020	24.80
14	F14	23/05/2020	30/05/2020	24.42
15	F15	23/05/2020	30/05/2020	24.56

Note: As per Indian Standards the concrete cube should attain the 99% strength for 28 days and 66% strength for 7 days.

*As Per client.

W. Malle
Professor & Head
Dept. of Civil Engineering
K.S. Group of Institutions
K.S. School of Engineering & Management
Bangalore-560 062.

tested by

B. Narayana



KSSEM

**K.S. GROUP OF INSTITUTIONS
K.S. SCHOOL OF ENGINEERING & MANAGEMENT**

#15/1, Mallasandra, Off. Kanakapura Main Road, Bengaluru - 560 109
Phone : 080 2842 5012, 2842 5013, 2842 5163 | Fax : 080 -2842 5164

8890

RECEIPT

No.

Date : 18/01/2020

Received From Mr. / Miss Sri Vatsa CV-Department

..... studying in B.E / MBA / M.Tech

a sum of Rupees four hundred fifty rupees only

towards the Library fine / Xerox / Shortage of attendance / lab. Breakage / Miscellaneous

Cube Testing

Rs. 450/-


Accountant

K S School of Engineering and Management

#15 MALLASANDRA, OFF, KANAKAPURA MAIN ROAD
Bangalore-560109

Department of Civil Engineering

Date: 17th Jan 2020


To
Sai Nandan Constructions,

3 sets of 3 concrete cubes were sent for compressive strength test. The test was conducted and results are described as below.

Date of testing: 17th Jan 2020

	Block no	Date of Cast	Weight (kg)	Max, load (kN)	Comp, Strength (N/mm ²)	Avg, Strength (N/mm ²)	Remarks
Set I	1	11/11/19	7.98	755.4	33.5	34.30	28 day strength
	2		8.18	669.8	29.7		M30
	3		8.00	894.3	39.7		
Set II	4	29/11/19	8.24	717.9	31.8	31.90	28 day strength
	5		7.97	696.5	30.9		M30
	6		7.99	742.7	33.0		
Set III	7	29/11/19	8.17	757.9	33.6	32.93	28 day strength
	8		8.00	708.6	31.4		M30
	9		8.00	762.6	33.8		


Faculty incharge


Head of Department

Professor & Head
Dept. of Civil Engineering
K.S. Group of Institutions
K.S. School of Engineering & Management
Bangalore-560062.

K S School of Engineering and Management

#15 MALLASANDRA, OFF, KANAKAPURA MAIN ROAD

Bangalore-560109

Department of Civil Engineering

Invoice

Date: 17th Jan 2020

To
Sai Nandan Constructions

Sl no	Date of testing	No of Cubes	Rate (Rs)	Amount (Rs)
1	17/01/2020	9	50	450
<i>Total</i>				<u>450</u>

Amount to be paid in words is **Four hundred and fifty**

huxelle

Head of the department

Professor & Head

Dept. of Civil Engineering

K.S. Group of Institutions

K.S. School of Engineering & Management

Bangalore-560 062.